
REVISIONS				APPROVALS		
DESCRIPTIONS	BY	DATE	APPROVED	COUNCIL RESOLUTION NO. 26-92 3/10/92		



- 1. SIDEWALKS SHALL BE CLASS B CONCRETE; A MINIMUM OF 4" THICK.
- 2. STRUCTURE BACKFILL MATERIAL A MINIMUM OF 4" IN DEPTH AND COMPACTED TO A MINIMUM OF 90% MAXIMUM DENSITY SHALL BE PLACED UNDER THE SIDEWALK WHEN THE SUBGRADE HAS AN R-VALUE OF LESS THAN 70.
- 3. 1/2" EXPANSION JOINTS SHALL BE PLACED AT ALL CURB RETURNS, DRIVEWAYS AND AT ALL INTERVALS NOT EXCEEDING 25'.
 1/2" x 18" SMOOTH, GREASED DOWELS 24" O.C. TO BE PLACED THROUGH THE EXPANSIVE JOINTS.
- 4. WEAKENED PLANE JOINTS SHALL BE A MINIMUM OF 1-1/4" IN DEPTH AT INTERVALS NOT TO EXCEED 5'.
- 5. SIDEWALK WIDTH IN COMMERCIAL AREAS TO BE DETERMINED BY THE ENGINEER.

DRAWN BY: R.A.L. DESIGNED BY:	CITY OF ATASCADERO ENGINEERING DEPARTMENT	DRAWING NO.
S.J.S. DATE: 2/27/92	SIDEWALKS	419
FÍLE NAME: AT419.DWG		